all extra charges will have to be borne by the contractor himself which will be recovered from the security deposit.

7. Once in a month, the tenderer will be paid through the Range Forest Officer for the value of the rations that may be supplied during the month on a bill to be prepared and sent to his office for sanction along with the receipts previously obtained by him for the supply of rations to the Range Officers after the bill is countersigned by the District Forest Officer.

8. The earnest money of the rejected tenderers will be returned to them immediately if they happen to be present at the time of opening of tenders and to others by post at their cost.

9. In all cases of disputes concerning the contract, the decision of the Conservator of Forests will be treated as final.

10. The contractor should also supply any special rations required whenever required at the current market rates.

11. For breach of any of the foregoing conditions, the District Forest Officer will be at liberty either to fine the contractor to the extent of Rs. 5 in each case or to cancel the contract at any stage and forfeit the deposit in full or part. The fine, if any levied on the contractor, will be recovered from the contractor's bill or security deposit.

12. The deposit of the contractor will be returned one month after the expiry of the contract period if the terms of the contract as per tender notification are fulfilled.

Form of Tender.

Sl. No.	Name of provision	Quantity	Rate	Remarks

H. S. RANGACHAR,
District Forest Officer.

ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 13th February 1940.

The attention of the public is hereby invited to the detailed notification, calling for tenders for constructing New Research Laboratory in the Serum Institute, Hebbal, Bangalore, published in pages 361-363, Part VI of the *Mysore Gazette*, dated 15th February 1940. The last date for receipt of tenders is 2nd March 1940.

Abstract Notification dated 12th February 1940.

The attention of the public is invited to the notification, calling for tenders for constructing a block of buildings in front of the existing blocks of the Middle School at Malleswaram, Bangalore City, on pages 363-365 of Part VI of the *Mysore Gazette*, dated 15th February 1940. The last date for receiving tenders is 8th March 1940.

Abstract Notification dated 21st February 1940.

The attention of public is hereby invited to the detailed notification, calling for tenders for constructing extensions to Chemistry Block to Central College, Bangalore, published in pages 415-416, Part VI of the *Mysore Gazette*, dated 22nd February 1940.

The last date of tender is 8th March 1940.

Abstract Notification dated 21st February 1940.

The attention of the public is hereby invited to the detailed notification, calling for tenders for extension to Physics Block of Cenrtal College, Bangalore, published in pages 417-418, Part VI of *Mysore Gazette*, dated 22nd February 1940.

The last date of tender is 9th March 1940.

Notification dated 20—24th February 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 2 P.M. on 16th March 1940, for constructing a new Building for Public Health Institute (Laboratory block,) Bangalore.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,250 (Rupees one thousand two hundered and fifty) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing new Public Health Institute Building, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Government who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any tender quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a new building for Public Health Institute Laboratory at Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
1	Earthwork excavation for foundation and filling in basement including removing the excavated earth to a distance of about 50 yards duly watering and tamping in layers of 6″ thick ..	C.yd.	0 3 6	542	
2	Granite jelly concrete in lime mortar of 1 : 2 : 4 for foundation (jelly of 1″ to 1½″ thick cubes) in layers of 6″ thick with consolidation ..	C.ft.	0 3 6	3,281	
3	Size stone in mortar for foundation with bond stones at every 6′ apart	,,	0 4 0	7,866	
4	Size stones quoins dressed in mortar basement with bond stones at every 6′ apart	,,	0 4 0	3,649	
5	Burnt stone slabs roughly dressed 6″ thick and two lines dressed to exposed faces as basement slabs fixed in lime mortar 1 : 3	S.ft.	0 4 9	1,471	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
6	Size stone in mortar for superstructure, courses should not be less than 8″ high with bond stones every 6′ apart, including quoin dressing ..	C.ft.	0 4 6	11,115·50	
7	Burnt brick in mortar for superstructure ..	,,	0 3 6	495	
8	Wire cut bricks in cement mortar of 1 : 3 with X-met at intervals of 4′	,,	0 14 0	498	
9	Teakwood doors $\frac{1}{3}$ panelled and $\frac{2}{3}$ glazed without sills with 3″×5″ frame work, $1\frac{1}{2}$″ thick shutters, with brass fittings..	S.ft.	1 10 0	624	
10	Teakwood windows with panelled shutters outside and glazed inside with 3″×5″ frame work, 1″ thick shutters with $\frac{3}{4}$″ M. S. bars 4″ apart with brass fittings, etc., complete	,,	2 13 0	943	
11	Teakwood ventilators of venetian type to be designed during execution	,,	2 0 0	290	
12	Teakwood ventilators glazed as per design to be furnished during execution	,,	1 4 0	30	
13	Flooring with cement concrete $1\frac{1}{2}$″ thick with a proportion of 1 : 2 : 4 on a bed of 3″ thick jelly lime concrete and finished with red ochre with lines cut as per required pattern	Sqr.	18 0 0	54·14	
14	R.C.C. roofing with a proportion of 1 : 2 : 4 including chajja with 3″ surki concrete, two courses of flat tiles and one inch plaster on top, complete ..	,,	60 0 0	88·44	
15	R.C.C. beams 9″ thick for main portion as per standard specifications, design furnished during execution	C.ft.	2 0 0	420	
16	R.C.C. slabs as lintels for openings of doors, windows, ventilators, etc., as per standard specifications, designed during execution ..	,,	2 0 0	316	
17	Burnt stone slabs 6″ thick, roughly dressed for the portions getting inside of walls and 2 line dressing to exposed faces as lintels over doors fixed in lime mortar 1 : 3	S.ft.	0 4 6	17	
18	Burnt stone slabs 4″ thick, 2 lines dressed to exposed faces, set in lime mortar 1 : 3 for sills of windows and ventilators	,,	0 4 6	311	
19	Plastering with lime mortar $\frac{3}{4}$″ thick	Sqr.	4 8 0	155·00	
20	Cement pointing to stone masonry with cement mortar 1 : 2 including raking out joints to a depth of $\frac{3}{4}$″	,,	3 0 0	72·64	
21	White washing two coats	,,	0 4 0	243·94	
22	Painting doors, windows, etc., with Government Lac Factory green paint, 2 coats	,,	4 8 0	51·18	
23	Providing and fixing down water pipes	R.ft.	0 8 0	146	

M. K. RAJAM IYENGAR,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 10th February 1940.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for restoring and improving Bettahalli Urumundinakere, Register No. 107, Kudur Hobli, Magadi Taluk, published in pages 358-360 of Part VI of the *Mysore Gazette*, dated 15th February 1940. The last date for the receipt of the tender is 2 P.M. on 4th March 1940. Duplicate challan for having credited the deposit money of Rs. 200 into the Treasury under 17 (*a*) P.W. Deposits should accompany each tender.

Notification dated 23rd February 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 16th March 1940, for Restoring Kayamgutta Kattariguppe Kannerkatte minor tank Reg. No. 62 of Bangalore Taluk.

2. Tenders in the prescribed form obtainable on payment of Re. 0-4-0 per form from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for restoring Kayamgutta Kattariguppe Kannerkatte minor tank Reg. No. 62 of Bangalore Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the Treasury the deposit amount of Rs. 210 under "17(*a*) P. W. Deposits" or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 16th March 1940 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of August 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Re. 1-6-0 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for restoring Kattriguppe Kannerkatte (Kayamgutta) Reg. No. 62 of Bangalore Taluk.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
	Bund.		Rs. a. p.		Rs.	Rs.
1	Clearing ordinary thin jungle at the bund with roots, etc.	Grade	1 0 0	8		
2	Cutting grips and trenches to the bund ..	„	2 0 0	8½		
3	Earthwork to bund with required lead and lift including watering and tamping, etc.	C.yd.	0 3 0	1,494		
4	Turfing the slopes and watering till it is satisfactory	S.yd.	0 0 9	2,072		
5	Removing and resetting the old stone revetment with new jelly wedging and jelly packing including required lead and lift	C.yd.	0 8 0	100		
6	New stone revetment with required lead and lift, jelly wedging and jelly packing, etc., complete	„	1 4 0	129		
7	Providing and fixing grade stones including carving figures and painting, etc., complete including bed slab	No.	1 8 0	9		
8	Providing and fixing Index stones including painting, etc.	„	0 6 0	9		
9	Providing and fixing Register No. stone on a bed slab including carving figures and painting, etc.	„	3 0 0	1		
10	Providing and fixing B. M. stones on bed slabs including carving figures, painting and masonry works, etc., complete ..	„	2 0 0	2		
11	Providing and fixing gauge stone on bed slab including carving figures and painting, etc., complete with masonry work..	„	10 0 0	1		

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
			Rs. a. p.		Rs.	Rs.
	Sluice.					
1	Earthwork cut opening the bund and refilling the same with watering and tamping, etc.	C.yd.	0 6 0	500		
2	Earthwork excavation for foundation and using the spoil to the bund with lead and lift	,,	0 4 0	100		
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	200		
4	Burnt brick in surki mortar	,,	0 4 6	100		
5	Burnt stone slabs 6″ thick exposed surfaces one line dressed and fixed in surki mortar	S.ft.	0 4 0	100		
6	Plastering with surki mortar	Sqr.	4 0 0	3·00		
7	Rough stone work with required lead and lift, jelly-backing and jelly-wedging, etc., complete	C.yd.	0 8 0	50		
8	Cutting holes in the slabs	Each	1 0 0	2		
9	Providing plug and rod with locking arrangement, etc., complete	,,	14 0 0	1		
10	Providing and fixing 4″ dia. cast iron pipes including jointing, carting, etc., complete	R.ft.	1 0 0	30		
	Waste Weir R. L. 50·00.					
1	Earthwork excavation and using the same for the bund	C.yd.	0 4 0	301		
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	727		
3	Size stone in surki mortar	,,	0 4 0	5,571		
4	Pointing with cement mortar	Sqr.	3 0 0	8·64		
5	New stone work with required lead and lift, jelly wedging and jelly packing, etc., complete	C.yd.	1 4 0	396		
6	Filling in with jelly and boulders below apron with lead and lift, etc. ..	,,	0 12 0	479		
7	Burnt stone slabs 6″ thick one line dressed and fixed in surki mortar and cement pointing, etc., complete	S.ft.	0 4 0	450		
8	Providing joggle joints, etc.	No.	0 8 0	37		

Notification dated 24th February 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 18th March 1940, for restoring Dandidass Kodagihalli Tank Reg. No. 192 of Dodballapur Taluk.

2. Tenders in the prescribed form obtainable on payment of Re. 0–4–0 per form from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for restoring Dandidass Kodagihalli Tank Reg. No. 192 of Dodballapur Taluk. The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the Treasury the deposit amount of Rs. 300 under 17 (a) P. W. Deposits or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 18th March 1940 at 3 P.M. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form,

for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 5 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 2 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for restoring Dandidass Kodagehalli Tank, Reg. No. 192 of Doddballapur Taluk.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
	Bund R. L. 57·00.		Rs. a. p.		Rs.	Rs.
1	Jungle clearing	Grade	0 8 0	26		
2	Cutting grips and trenches	,,	1 8 0	24		
3	Removing ant-hills and filling gravel	No.	1 0 0	4		
4	Earthwork to bund with required lead and lift, watering and tamping, etc., complete.	C.yd.	0 3 6	12,485		
5	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	0 1 0	7,738		
6	Removing and resetting old stone work with new jelly backing, jelly wedging, including lead and lift	C.yd.	0 14 0	190		
7	Rough stone work with jelly backing and jelly wedging including required lead and lift, etc.	,,	1 12 0	243		
8	Removing and refixing old grade stones on bed slabs, etc., including figuring and painting	No.	1 0 0	20		
9	Providing and fixing new grade stones on bed slabs including figuring and painting, etc.	,,	1 8 0	9		
10	Providing and fixing Index stones, etc.	,,	0 6 0	29		
11	Removing and refixing old Register No. stone on bed slabs, with figuring and painting, etc.	,,	1 0 0	1		
12	Providing and fixing gauge stone on a bed slab with masonry work, figuring and painting, etc., complete	,,	15 0 0	1		
13	Gravel backing to revetment with required lead and lift	C.yd.	0 8 0	81		
	Sluice portion.					
1	Earthwork cut open the bund and refilling, with watering and tamping, etc., complete.	C.yd.	0 3 0	605		
2	Removing and resetting old stone work with new jelly backing and jelly wedging including required lead and lift	,,	0 14 0	120		
3	Turfing and watering till it is satisfactory	S.yd.	0 1 0	219		
4	Providing teakwood plug and iron rod, with locking arrangement, etc., complete	No.	20 0 0	2		
5	Size stone in surki mortar	C.ft.	0 5 0	50		
6	Burnt stone slabs 6" thick, one line dressed and fixed in surki mortar	S.ft.	0 4 6	75		
7	Surki mortar plastering	Sqr.	3 8 0	3·00		
	Weir.					
1	Removing and replacing old coping slabs in surki mortar	S.ft.	0 2 0	238		
2	Size stone in surki mortar	C.ft.	0 5 0	2,799		
3	Pointing with surki mortar	Sqr.	2 8 0	23·49		
4	Burnt jelly concrete in surki mortar with plastering, etc.	C.ft.	0 4 0	135		
5	Earthwork excavation for foundation, etc.	C.yd.	0 3 0	285		
6	Rough stone work with jelly backing and jelly wedging including required lead and lift	C.yd.	1 12 0	237		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.